



ગુજરાત ગ્રામીણ બેંક
GUJARAT GRAMIN BANK
Scheduled Bank Owned by Government

**TENDER FOR FURNISHING WORKS OF MALIYA HATINA BRANCH AT
NEW PREMISES OF
GUJARAT GRAMIN BANK.**

PRICE BID
(ENVELOPE-2)

LAST DATE OF SUBMISSION : AS PER NOTICE INVITING TENDER (NIT)

**Tender will be addressed to "The Regional Manager, Gujarat Gramin Bank,
Region Office - Junagadh, 4th Floor, Vinayak Prime A, Opp. Kulp Hospital,
Vanthali Road - Junagadh - 362015, Gujarat".**

Tenders will be submitted at the following address

**GUJARAT GRAMIN BANK,
REGION OFFICE - JUNAGADH,
4TH FLOOR, VINAYAK PRIME A, OPP KULP HOSPITAL
VANTHALI ROAD – JUNAGADH - 362015,
GUJARAT.**

**ARCHITECT:
AR.HASIT KHOLIA
407,COSMO COMPLEX,
NEAR MAHILA COLLEGE UNDER BRIDGE
RAJKOT – 360001,
GUJARAT
MOB: 9825217626
EMAIL: HASITKHOLIA@GMAIL.COM**



CONSOLIDATED TENDER SUMMARY

Sr.	Part Description			Rate (Rs.)	Amount (Rs.)
A	PART A - INTERIOR FURNISHING & ALLIED WORKS			Rs.	

GRAND TOTAL (PART A)**Rs.**


ALL RATES SHALL BE QUOTED EXCLUDING GST. GST, AS APPLICABLE, WILL BE PAID SEPARATELY AT THE TIME OF BILLING.



PROPOSED INTERIOR FURNISHING AND ALLIED WORKS OF GUJARAT GRAMIN BANK FOR MALIYA HATINA BRANCH AT NEW PREMISES

MALIYA HATINA BRANCH

Sr. No.	Description	Quantity	Unit	UNIT RATE (Rs.)	AMOUNT (Rs.)
Note :	RATES SHALL BE INCLUSIVE OF MATERIALS, LABOUR, TOOLS, MACHINERY, SCAFFOLDING, FINAL DISPOSAL OF DEBRIS, CLEANING, CUTTING, WASTAGE, TRANSPORTATION AND ALL APPLICABLE TAXES/DUTIES/LEVIES, EXCEPT GST. GST, AS APPLICABLE, WILL BE PAID SEPARATELY AT THE TIME OF PAYMENT OF BILLS.				
[A]	FURNISHING WORK				
1	SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White corian & blue lacquered glass finishing	0.00	RMT		
	Supplying, fixing and keeping in position single window counter complete as per design and drawing made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
[a]	size :				
	Description: L B Ht.				
	Writing Top 5'-0" 2'-9" 2'-6"				
	4 Drawers with				
	pigeon hole 2'-0" 1'-3" 2'-0"				
	Computer key Board with mouse				
	Supplying and fixing metal key Board of approved make in counter as per design and instructions.				
[b]	Working table top and edges shall be finished with 6 mm thick white corian of DUPONT or equivalent approved make as per drawing and direction with all labour and material.				
[c]	FRONT APRON : 2 NOS 6 MM THICK FLEXY PLY WOOD IN ROUND SHAPE WITH 6 MM THICK WHITE CORIAN SHALL BE PROVIDED AT FRONT AS PER DESIGN. ALL EDGES SHOULD BE FINISHED WITH CORIAN OF DUPONT MAKE.				
[d]	FRONT PANEL SHALL BE FINISHED WITH 6 MM THICK 18" HIGH BLUE BACK PAINTED GLASS OF APPROVED MAKE AND FIXED ON 18 MM THICK COMMERCIAL PLY WOOD WITH NATURAL SILICON GUM AS PER MANUFACTURER'S SPECIFICATION AND TO BE COMPLETED AS PER DRAWING				




[e]	Foot rest of 3" x 1.5" in C.P. Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 16" x 24"				
[f]	ALL WOOD WORK SHALL BE LACQUER POLISHED TO A SMOOTH AND UNIFORM FINISH OF CHOICE COLOUR AND SHADE.				
[g]	All fittings like S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
[h]	Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.				
[i]	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete				
[j]	Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid (FOR DETAILS REFER DRG. NO- 1)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 6 mm thick white corian				
	2) FRONT APRON: ROUND CORIAN AND 6 MM THICK BACKPAINTED BLUE GLASS FIXED WITH NATURAL SILICON				
	3) Facing of Drawers: 1.00 mm thick laminate finish				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
1[a]	SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with Matt finish laminate	1.50	RMT		
	SAME AS ABOVE ITEM NO-1 BUT PROVIDING 0.80 MM THICK MATT FINISH SUPERWHITE LAMINATE AICA MAKE-UGM G 324/1324 OR EQUIVALENT INSTEAD OF WHITE CORIAN AND 1.00 MM THICK MATT FINISH SAPPHIRE BLUE LAMINATE AICA MAKE- G 452/1452 INSTEAD OF BLUE LACQUERED GLASS ETC COMPLETE AS DIRECTED				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 0.80 mm thick matt finish laminate				
	2) FRONT APRON & PANEL : ROUND MATT FINISH WHITE LAMINATE AND 1.00 MM THICK SAPPHIRE BLUE LAMINATE				
	3) Facing of Drawers: 1.00 mm thick laminate finish				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
1[b]	Providing and fixing 12 mm thick Toughened Glass partition on counter top, front side as follows.	1.14	SQMT		
	Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary S.S Brush finish brackets & support on wooden partition as directed with necessary cut out in glass. All edges of glass shall have Diamond cut polished edges as directed. [REFER DRG NO-1]				




1[c]	Providing and fixing 12mm thick Toughened float Glass partition between Single Window counters as follows.	0.00	SQMT		
	12 MM THICK TOUGHENED CLEAR FLOAT GLASS WITH POLISHED EDGES SHALL BE FIXED WITH SILICON AND T.W BEADING SUPPORT ON WOODEN PARTITION AS DIRECTED. ALL EDGES OF GLASS SHALL BE DIAMOND CUT POLISHED EDGES AS DIRECTED COMPLETE. WOODEN PARTITION WILL BE PAID SEPARATELY. MAXIMUM LENGTH AND HEIGHT WILL BE MEASURED FOR PAYMENT PURPOSE, REFER DRG NO-1				
	TABLES				
2	R.MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT. with 3.5 mm thick Teak veneer with PU coating finish on Table Top , sides & Edges and all other visible surfaces etc complete as follows	0.00	NO		
	SUPPLYING AND INSTALLATION OF TABLE AS PER THE FOLLOWING DESCRIPTION : SIZE 6'-0" X 2'-9". TABLE TOP SHALL BE MADE FROM 18 MM THICK COMMERCIAL PLY WOOD WITH 3.50 MM THICK TEAK VENEER WITH PU COATING WITH NECESSARY INTERMEDIATE SUPPORT. TABLE TOP SHALL BE SUPPORTED BY 18 MM THICK COMMERCIAL PLY WOOD WITH WOODEN FRAMING. STORAGE CABINET OF 1'-3" X 2'-0" X 2'-6" SHALL BE PROVIDED USING 18 MM THICK COMMERCIAL PLY WOOD HAVING 4 NOS DRAWERS AS DIRECTED WITH HEAVY DUTY TELESCOPE SLIDING CHANNEL OF APPROVED MAKE , GROUP LOCK, S.S. HANDLE. COMPUTER KEY BOARD OF METAL OF APPROVED MAKE SHALL BE PROVIDED. EXPOSED SURFACES OF THE CABINET SHALL HAVE TEAK VENEER WITH PU POLISH . FOOT REST OF 1 1/2" X 3" T.W MEMBERS SHALL BE PROVIDED. ALL INTERNAL SURFACE WILL HAVE 0.60 MM THICK BALANCING LAMINATE				
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with teak veneer PU Finish & groove pattern as per drawing				
	Table side made from 18 mm thick ply wood with 3.50 mm thick teak veneer with PU coating finish shall be provided in a pattern as per drawing. Veneer to be provided on all visible surfaces.				
	DRAWER FASCIA MADE OUT OF 18 MM THICK PLYWOOD. THE SIDES/BACK/BASE OF DRAWERS BE MADE OF 12 MM THICK PLY WOOD & BOTTOM OF DRAWERS SHALL BE OF 6 MM THICK PLY WOOD. FIXING VENEER ON FRONT SIDE AND ALL THE INTERNAL SURFACES SHALL BE 0.60 MM THICK BALANCING LAMINATE. THE DRAWERS TO BE FITTED WITH TELESCOPIC SLIDING CHANNEL WITH SS GROUP LOCKS OF APPROVED MAKE AND 100 MM LONG BRUSH FINISH STAINLESS STEEL HANDLES FOR EACH DRAWER. ALL THE EDGES OF DRAWER FASCIA BE PROVIDED WITH TEAK WOOD EDGE BENDING WITH LACQUER POLISHED ETC COMPLETE AS DIRECTED.				
	TABLE SHALL HAVE STAND FOR KEEPING CPU AND METALLIC CABLE MANAGER SHALL BE PROVIDED IN TABLE TOP. ALL EXPOSED EDGES OF PLYWOOD SHALL HAVE VENEER WITH SMOOTH EDGES & CORNERS				




	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade. Etc. complete.				
	All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade				
	As per drawing and instruction of Architect/Bank work to be Completed (FOR DETAILS REFER DRG. NO- 2)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 3.5 mm thick Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating				
	2) FRONT APRON & SIDES: 3.5 MM THICK TEAK VENEER WITH PU COATING				
	3) Facing of Drawers: 3.5 mm thick Teak Veneer with PU Coating				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
2[a]	Same as above Item no 2 but size 5'-0" x 2'-6" with storage unit 4 Nos Drawer in table With Top Veneer finished & other surfaces 1.0 mm thick laminate finished (FOR DETAILS REFER DRG. NO-3)	0.00	NO		
2[b]	Same as above Item no-2 but Size: 4'-6"x2'-6" with 4 nos Drawer Unit With Top Veneer finished & other surfaces 1.0 mm thick laminate finished	0.00	NO		
2[c]	Same as above Item no-2 but Size: 4'-0"x2'-0" with 4 nos Drawer Unit With Top Veneer finished & other surfaces 1.0 mm thick laminate finished	0.00	NO		
2[d]	Same as above Item no-2, but size 6'-0"x 2'-9" all external surfaces including top to be finished with 1 mm thick Laminate (approved shades)	1.00	NO		
2[e]	Same as above Item-no-2 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	6.00	NO		
2[f]	Same as above Item no-2 but Size: 4'-6"x2'-6" with 4 nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces	0.00	NO		
2[g]	Same as above Item no-2 but Size: 4'-0"x2'-0" with 4 nos Drawer Unit with laminate finish on all exposed surfaces	0.00	NO		



2[h]	Same as above Item no-2 but Size: 4'-6"x 2'-6" Without Drawer Unit With Top Veneer finished & other surfaces 1.0 mm thick laminate finish on all exposed surfaces [REFER DRG NO-4]	0.00	NO		
2[i]	SAME AS ABOVE ITEM NO-2 BUT SIZE: 4'-0"x 2'-0" WITHOUT DRAWER UNIT WITH TOP VENEER FINISHED & OTHER SURFACES 1.0 MM THICK LAMINATE FINISHED ON ALL EXPOSED SURFACES	0.00	NO		
2[j]	Same as above item no-2 but Size: 4'-6"x2'-6" without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces	0.00	NO		
2[k]	Same as above item no-2 but Size: 4'-0"x2'-0" without Drawer Unit with 1.0 mm thick Laminate finished on all exposed surfaces	0.00	NO		
3	Linear Table with Drawer (Laminate Finish on Table Top and Drawer shutter)	0.00	RMT		
	PROVIDING AND FIXING LINEAR TABLE HAVING WIDTH OF 2'-0" USING 18 MM THICK COMMERCIAL PLYWOOD FOR TOP AND VERTICAL SUPPORT AT 4'-0" C/C, PROVIDING STORAGE CABINET TWO DRAWER AND ONE SHUTTER UNIT AT EVERY 4'-0" C/C, GROUP LOCK, SS HANDLE IN COUNTER AS DIRECTED COMPLETE. 1.0 MM THICK LAMINATE FINISH ON TABLE TOP AND FRONT SIDE OF SHUTTER. PROVIDING FOOT REST OF 3" X 1.5" IN C.P. TEAK WOOD WITH LACQUERED POLISH. ALL INTERNAL SURFACES SHALL HAVE 0.60 MM THICK BALANCING LAMINATE AS DIRECTED.				
3[a]	Providing and Fixing Linear Work Station Table WITHOUT STORAGE UNIT	0.00	RMT		
	P/F Linear/Running counter table Same as above Item No-3 but size 2'-0" wide & without Drawer in table Finishing as follows same above				
	[FOR DETAIL REFER DRG NO-09]				
	(Low height partitions above the counters Table top shall be paid separately.)				
	FINISHING DETAILS IN NUTSHELL:				
	1) TABLE TOP : DARK LAMINATE & TEAK WOOD BEADING ON EDGES WITH POLISHED FINISH				
	2) Sides: Frosty White Laminate				
	3) All the internal surface shall be provided with 0.60 mm thick balancing laminate.				
3[b]	Providing and Fixing Linear Work Station Table WITHOUT STORAGE UNIT Size: 8'-0"x 4'-0" for 4 Nos seating (Rate for 4'-0' wide Table)	0.00	RMT		
	P/F LINEAR/RUNNING COUNTER TABLE SAME AS ABOVE ITEM NO-3[A] BUT SIZE 4'-0" WIDE WITH VERTICAL PARTITION IN CENTER MADE OF 6 MM THICK PLY HAVING BALANCING LAMINATE BOTH SIDES & WITHOUT DRAWER IN TABLE.				
	[FOR DETAIL REFER DRG NO-10]				



	(Low height partitions above the table top shall be paid separately.)				
3[c]	PEDESTAL [DRAWER BOX] Approx. Size 400mm W x 450mm Dx 680mm H	0.00	NO		
	THE PEDESTAL UNIT SHALL HAVE OVERALL OUTER DIMENSIONS AS 400 Wx450 Dx680 H MM AND OUTER BOX & DRAWER FASCIA MADE OUT OF 18 MM THICK PLYWOOD. THE DRAWER UNIT SHALL HAVE 2 BOX DRAWER & 1 FILING DRAWER. THE SIDES/BACK/BASE OF DRAWERS BE MADE OF 12 MM THICK PLYWOOD & BOTTOM OF DRAWERS SHALL BE OF 6 MM THICK PLYWOOD. FIXING 1.0 MM THICK LAMINATE ON ALL EXTERNAL FOUR SIDES & TOP AND ALL THE INTERNAL SURFACES (NON VISIBLE SURFACES) SHALL BE 0.60 MM THICK BALANCING LAMINATE. THE FILING DRAWER TO FITTED WITH TELESCOPIC SLIDING CHANNEL & BOX DRAWERS WITH ROLLER SLIDES OF SELF-CLOSING ACTION WITH SS GROUP LOCKS OF APPROVED MAKES AND 100 MM LONG BRUSH FINISH STAINLESS STEEL HANDLES FOR EACH DRAWER. ALL THE EDGES OF DRAWER FASCIA BE PROVIDED WITH TEAK WOOD EDGE BENDING WITH LACQUER POLISHED ETC COMPLETE AS DIRECTED.				
4	GRAHAK MITRA TABLE OF 2'-3" WIDE with PU coating finish	0.00	RMT		
	Same as above item no 2 but Size 2'-3" wide with storage unit in Table with 4mm thick MDF board + Blue and white PU Coating finishing on all exposed visible surface as per drawing and instruction of Architect/Bank For Grahak Mitra/Tech Mitra (Help Desk Table)				
	Table top made from 18 mm thick ply wood + 4mm thick MDF board with PU coating finish				
	Apron (Front side) made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
	Both sides made from 18 mm thick ply wood + 4mm MDF board with PU Coating finish				
	3" thick Partition above working table top made from 18 mm thick+6 mm thick ply wood with necessary framing with 4mm thick MDF board + PU Coating finish as per drawing.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 18 mm Thick Plywood with 4 mm thick MDF with High gloss white PU Coating				
	2) FRONT APRON & SIDES : 4MM THICK MDF WITH HIGH GLOSS WHITE/BLUE PU COATING				
	3) Facing of Drawers : 1.0 mm thick Laminate finish				



4[a]	RECEPTION TABLE - (6.75' X2'6")	0.00	RMT		
	IN LAMINATE FINISH				
	PROVIDING AND MAKING A TABLE OF OVER ALL SIZE OF TOP AS MENTIONED ABOVE AND AS PER DESIGN GIVEN. IT SHALL CONSIST OF 18MM THK. COMM. PLY TOP FINISHED WITH GALAXY MARBLE 12MM (ENGG. MARBLE) THICK / CORIAN OF 4MM THICK WITH EDGE MOULDING AND A 3 DRAWER UNIT WITH LOCKS, HANDLES ETC. ON THE END OF THE TABLE AS SHOWN IN THE DRAWING.(AS APPROVED BY BANK / ARCHITECT). THE DRAWER UNIT FINISHED TOP SHOULD BE AT A LOWER LEVEL OF 25MM BELOW THE FINISHED COUNTER TOP. THE FRONT MODESTY PANEL SHOULD BE FINISHED 18 MM COMM. PLY WITH LAMINATE (AS APPROVED COLOUR / SHADE) WITH METALLIC LAMINATE. THE CUSTOMER SIDE TOP SHOULD BE AT A HEIGHT OF 1 FEET WITH 18MM THICK PLY ABOVE WHICH GALAXY MARBLE (ENGG.MARBLE)/CORIAN OF 4MM THICK OF APPROVED COLOUR TO BE PROVIDED. THE INSIDE OF DRAWER UNITS, AND THE TABLES SHOULD BE FINISHED WITH LAMINATE OF APPROVED SHADE.				
5	DINING TABLE Approx Size 5'-0"/ 6'-0"x 3'-0"	0.00	SQMT		
	Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	SIDE CREDENZA (SIDE TABLE)				
7	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 3.50 mm thick Teak veneer with PU Coating finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges with PU Coating. Veneer to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose. (For BM) Rate for length Less then 3'-3" length	0.00	SQMT		



7[a]	SUPPLYING AND INSTALLATION SIDE CABINET FOR KEEPING COMPUTER AND PRINTER OF SIZE 1'-4" WIDTH 2'-6" HEIGHT AND 3'-6" LENGTH HAVING OPENABLE SHUTTERS AS DIRECTED. CABINET SHALL BE MADE FROM 18 MM THICK COMMERCIAL PLY WOOD WITH 3.50 MM THICK VENEER WITH PU FINISH. BACK SHALL BE MADE FROM 6 MM THICK COMMERCIAL PLYWOOD. OPENABLE SHUTTERS SHALL BE MADE FROM 18 MM THICK COMMERCIAL PLY WOOD WITH VENEER FINISHED AND APPROVED MAKE GROUP LOCK, HANDLE, HINGES, MAGNET CATCH. , RATE INCLUDES ALL NECESSARY PROVISIONS FOR INSTALLING COMPUTERS. ALL THE INTERNAL SURFACE, BACK SIDE SHALL HAVE 0.60 MM THICK BALANCING LAMINATE				
7[b]	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
7[c]	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
7[d]	SIDE CREDENZA (SIDE TABLE) WITH PARTLY DRAWERS SAME AS ABOVE ITEM No. 7, BUT ALL EXTERNAL SURFACES TO BE FINISHED WITH 1.0 MM THICK LAMINATE (APPROVED SHADES). SIZE SHALL BE 3'-0"/3'-3" X 1'-4" X 2'-6" HT. WITH PARTLY DRAWERS & PARTLY OPENABLE SHUTTERS AS DIRECTED	2.28	SQMT		
	FINISHING DETAILS IN NUTSHELL:				
	1) TOP : DARK LAMINATE & BURMA TEAK BEADING ON EDGES WITH POLISHED FINISH				
	2) FRONT APRON & SIDES: AS PER ARCHITECT INSTRUCTION				
7[e]	SIDE CREDENZA (SIDE TABLE) FOR S.W COUNTER SAME AS ABOVE ITEM No-7 BUT SIDE TABLE TOP AND EDGES SHALL BE FINISHED WITH 6 MMTHICK WHITE CORIAN ON TOP AND EDGES. ALL OTHER VISIBLE SURFACE SHALL BE FINISHED WITH 1.00 MM TH LAMINATE. SIZE SHALL BE 3'-0"x 1'-4"x2'-6" HT. WITH OPENABLE SHUTTER AS DIRECTED	0.00	SQMT		
7[f]	STORAGE CABINET with Top & Front laminate finished. Storage of any height	36.77	SQMT		
	Same as above Item No-7, but all external surfaces to be finished with Laminate (approved shades)				
	FINISHING DETAILS IN NUTSHELL:				
	1) TOP : DARK LAMINATE & BURMA TEAK BEADING ON EDGES WITH POLISHED FINISH				
	2) FRONT APRON & SIDES: DARK LAMINATE/FROSTY WHITE LAMINATE AS PER DESIGN & INSTRUCTIONS				
7[g]	P/F ELECTRIC CUB BOARD	5.00	SQMT		




	PROVIDING AND FIXING ELECTRIC CUP BOARD USING 18 MM THICK BISON BOARD FOR INSIDE VERTICAL DIVISION, SHELVES AND SHUTTER. ALUMINIUM FRAMING OF 50x25x1.20MM THICK WITH 6 MM THICK BISON BOARD ON BOTH SIDE FOR OUTER PARTITION WITH 1.0 MM THICK LAMINATE ON ALL EXPOSED SURFACE AND POLISHING/ SYNTHETIC ENAMAL PAINT ON ALL INTERNAL SURFACE. SHUTTER WILL HAVE APPROVED MAKE LOCK, HANDLE, HINGES, BALL CATCHES & S.S PERFORATED JALI ETC.COMPLETE AS DIRECTED. DEPTH OF CUP BOARD WILL BE AROUND 1'-3". HEIGHT OF SHUTTER WILL BE MAXIMUM 7'-0". ONLY FRONT ELEVATION SHALL BE MEASURED FOR PAYMENT PURPOSE.				
7[h]	P/F PANTRY PLATFORM CUB BOARD SHUTTER	1.50	SQMT		
	PROVIDING AND FIXING CUPBOARD SHUTTERS BELOW PANTRY PLATFORM USING 1 1/2" x 2 1/2" SECOND GRADE T.W MEMBERS FOR FRAME, 18 MM Tk PLYWOOD WITH 1.0 MM LAMINATE FOR SHUTTERS. PROVIDING 1/2" TH T.W BEADING ALL AROUND SHUTTER. PROVIDING S.S HINGES, HANDLES, STOPPERS AND MAGNETIC CATCH AS DIRECTED. ALL THE WITHOUT LAMINATE SURFACE SHALL BE POLISHED/ SYNTHETIC ENAMAL PAINT AS DIRECTED COMPLETE.PROVIDING AND FIXING 0.60 MM THICK BALANCING LAMINATE ON INTERNAL SHUTTER SURFACE				
	LOW HEIGHT PARTITION WORK				
8	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR BACK SIDE AND IN BETWEEN S.W COUNTER AND CASH CABIN WITH TOUGHENED GLASS	4.35	SQMT		
	PROVIDING AND FIXING LOW HEIGHT PARTITION USING 50MM X 25MM X 1.50MM THICK ALUMINIUM MEMBERS MAXIMUM IN GRID OF 2'-0" X 2'-0" FIXING 12 MM THICK MDF BOARD EXTERIOR GRADE / 6 MM THICK PLY OF APPROVED BRAND ON BOTH SIDE OF ALUMINIUM FRAMING AND FIXING 1.0 MM THICK LAMINATE OF APPROVED SHADE ON BOTH SIDES, FIXING 12 MM THICK TRANSPARENT TOUGHENED GLASS AS DIRECTED. APPLYING POLISH ON EXPOSED STEAM BEECH MEMBERS WITH LACQUER POLISHED EDGES AS DIRECTED. LAMINATE TO BE PROVIDED ONLY ON VISIBLE SURFACE [FOR DETAILS REFER DRG. NO- 1] THE QUOTED RATE SHALL BE APPLICABLE FOR EITHER OF THE SPECIFIED BOARD OPTIONS AS DIRECTED BY THE ARCHITECT/BANK, WITH NO EXTRA PAYMENT.				
	For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.				
8[a]	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE	0.00	SQMT		
	SAME AS ITEM NO 10 BUT P/F 30 / 32 MM THICK FLUSH SHUTTER WITH BOTH SIDE LAMINATE INCLUDING SS HINGES WITH COUNTERSUNK SS SCREWS, APPROVED MAKE NIGHT LATCH LOCK, S.S HANDLES, DOOR STOPPERS, DOORSTOP ETC COMPLETE AS DIRECTED.				




8[b]	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION WITH CLEAR FLOAT GLASS	1.85	SQMT		
	PROVIDING AND FIXING LOW HEIGHT PARTITION USING 50MM X 25MM X 1.50MM THICK ALUMINIUM MEMBERS MAXIMUM IN GRID OF 2'-0" X 2'-0" FIXING 12 MM THICK MDF BOARD EXTERIOR GRADE / 6 MM THICK PLY OF APPROVED BRAND ON BOTH SIDE OF ALUMINIUM FRAMING AND FIXING 1.0 MM THICK LAMINATE OF APPROVED SHADE ON BOTH SIDES. FIXING 12MM THICK FREE CLEAR FLOAT GLASS AS DIRECTED. APPLYING LACQUER POLISH ON EXPOSED STEAM BEECH MEMBERS / EDGES AS DIRECTED. LAMINATE TO BE PROVIDED ONLY ON VISIBLE SURFACE PROVIDING PINUP BOARD OF SOFT BOARD COVERED WITH FABRIC AND FIXED IN PARTITION AS PER DESIGN/INSTRUCTION COMPLETE AS DIRECTED. THE QUOTED RATE SHALL BE APPLICABLE FOR EITHER OF THE SPECIFIED BOARD OPTIONS AS DIRECTED BY THE ARCHITECT/BANK, WITH NO EXTRA PAYMENT.				
	FULL HEIGHT PARTITION WORK				
9	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR	34.56	SQMT		
	PROVIDING AND FIXING BOTH SIDES LAMINATE FULL HEIGHT PARTLY GLAZED PARTITION USING 50MM X 25MM X 1.50MM THICK ALUMINIUM MEMBERS IN A MAXIMUM GRID OF 2'-0" X 2'-0" FIXING 12 MM THICK MDF BOARD EXTERIOR GRADE / 6 MM THICK PLY ON BOTH SIDES, 1.0 MM LAMINATE OF APPROVED MAKE SHALL BE FIXED ON MDF / PLYWOOD. PROVIDING AND FIXING 5.0/8.0 MM THICK FLOAT GLASS AS DIRECTED IN THE PARTITION. PROVIDING AND FIXING DOOR SHUTTER USING 32 MM THICK FLUSH SHUTTER BOTH SIDE LAMINATED AND FIXING 6 MM THICK GLASS WITH BEADING PATTI, 5" LONG 3 NOS STAINLESS STEEL HINGES, DOORSTOP SHALL BE PROVIDED AS DIRECTED. GODREJ MORTICE LOCK SHALL BE PROVIDED IN DOOR SHUTTER. ALL VISIBLE MEMBERS IF NOT LAMINATED SHALL HAVE LACQUER POLISHED AS DIRECTED. [REFER DRG NO-5] THE QUOTED RATE SHALL BE APPLICABLE FOR EITHER OF THE SPECIFIED BOARD OPTIONS AS DIRECTED BY THE ARCHITECT/BANK, WITH NO EXTRA PAYMENT. THE QUOTED RATE SHALL COVER EITHER GLASS THICKNESS SPECIFIED ABOVE, AS DIRECTED BY THE ARCHITECT/BANK, WITH NO EXTRA PAYMENT.				
	FOR PURPOSE OF PAYMENT PARTITION HEIGHT UP TO BOTTOM OF FALSE CEILING ONLY SHALL BE MEASURED AND PAID . NO EXTRA PAYMENT SHALL BE MADE FOR MEMBERS GOING UP TO SLAB/BEAM BOTTOM.				



9[a]	SLIDING/FOLDING FULL HEIGHT PARTLY GLAZED PARTITIONS : PROVIDING AND FIXING IN POSITION SLIDING FOLDING SOLID / PARTLY GLAZED FULL HEIGHT PARTITION IN HETTICH SLIDING IN LINE ACCSORIES FRAME WORK AS SHOWN IN THE DRAWING EXCLUDING DOOR AS SHOWN IN THE DRAWING IN FRAME WORK AT 2'x 2' GRID (HORIZONTALLY AND VERTICALLY) COMPRISING OF 2" x 1½" T.W. /STEAM BEECH SECTION/OR 2" x 1-1.5" ALUMINIUM FRAME WITH 6MM PLYWOOD ON BOTH SIDES FINISHED WITH 1MM THICK LAMINATES OF APPROVED SHADE AND COLOR AS SHOWN IN DRAWINGS. PARTITION TO INCLUDE 8MM MM THICK GLASS WITH FROSTING AS PER DESIGN AND 2" x 2" T.W. /STEAM BEECH MEMBER FOR DOOR SIDES AND GLASS SIDES AND T.W./STEAM BEECH DOOR FRAME TO TAKE 8MM THICK GLASS WITH FROSTING & 2" x 2" T.W./STEAM BEECH MEMBER FOR DOOR FRAME. ALL EXPOSED T.W./STEAM BEECH SURFACES TO BE FINISHED IN MELAMINE POLISH OF MATCHING LAMINATE COLOR AS DIRECTED INCLUDING ALL NECESSARY STAINLESS STEEL FINISH FITTING/ HARDWARE, AND WOOD PRESERVATIVE PAINT ETC. AS PER LIST OF APPROVED MATERIAL AND AS APPROVED BY THE PROJECT CONSULTANT /BANK, COMPLETE IN ALL RESPECTS.(NOTE: IN CASE OF FALSE CEILING, THE VERTICAL T.W. MEMBER TO BE FIXED WITH PUCCA CEILING BUT THE AREA OF PARTITION PAYABLE WILL BE BELOW THE FALSE CEILING ONLY).COMPLETE AS PER DRAWING AND AS DIRECTED BY THE ARCHITECT.	0.00	SQMT		
9[b]	Providing and Fixing Partition For Server Room/UPS Room Same as above item no 9 but Providing both side 8 mm thick Hilux board over aluminium framing with plastic paint of approved make & specifications etc complete as directed.	0.00	SQMT		
10	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.	12.35	SQMT		
	PROVIDING AND FIXING 4"x2" STEAM BEECH MEMBER FOR FRAME AND FLUSH DOOR SHUTTER MADE OUT OF 32 MM THICK FLUSH DOOR WITH 6 MM THICK CLEAR FLOAT GLASS VISION PANEL SECURED WITH 12 MM THICK STEAM BEECH BEADING, 32 X 12 MM THICK STEAM BEECH PERIPHERY PATTI AROUND SHUTTER EDGES, 1 MM THICK LAMINATE ON BOTH SIDES, 35X12MM THICK STEAM BEECH STOPPER PATTI ON FRAME INCLUDING 3 Nos 5" LONG SS HINGES WITH COUNTERSUNK S S SCREWS, APPROVED MAKE DEAD LOCK, S.S HANDLES, 150 MM LONG DOOR STOPPERS, DOORSTOP OF APPROVED MAKE ETC. ALL EXPOSED SURFACE /EDGES NOT LAMINATED BE PROVIDED WITH LACQUER POLISH. WORK TO BE COMPLETED AS PER DRAWING & INSTRUCTIONS [REFER DRG NO-5]				
10[a]	Providing and fixing UPS door shutter with Aluminium Frame and both side Hilux sheet	1.89	SQMT		



	PROVIDING AND FIXING DOOR SHUTTER MADE OUT OF 50x25x1.5MM THICK ALUMINIUM FRAMING AT MAXIMUM 1'-6" C/C BOTH WAY WITH 8 MM THICK HILUX BOARD ON BOTH SIDE WITH PAINTING. PROVIDING 6 MM THICK CLEAR FLOAT GLASS VISION PANEL SECURED WITH 12 MM THICK STEAM BEECH BEADING. STEAM BEECH BEADING OF SIZE 31x12 MM SHOULD BE PLACED AROUND SHUTTER EDGES, ALUMINIUM STOPPER PATTI ON FRAME INCLUDING 3 NOS 5" LONG SS HINGES WITH COUNTERSUNK SS SCREWS, APPROVED MAKE DEAD LOCK, S.S HANDLES, DOOR STOPPERS, DOORSTOPPER TO BE FIXED AS PER DRAWING & INSTRUCTIONS. ALL BEADINGS SHOULD BE POLISHED.				
	GLASS DOORS AND PARTITIONS				
11	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door	2.52	SQMT		
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.				
11[a]	Same as above item but P & F FULLY GLAZED PARTITION With Patch Fitting for front side of Main Entrance [FIXED PORTION] For Branch and E-Lobby	9.05	SQMT		
11[b]	PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHARM FOR SEPARATING TWO M/C FOR E-LOBBY	0.00	SQMT		
	P /F 12mm th Toughened glass Diapharm between two machines with etching and frosting Films complete as directed. Glass edges shall be round moulded and polished as per direction. Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid).				
	PANELLING WORK				
12	P/F Wall panelling with laminate finishing for wall and Pillar etc	37.00	SQMT		




	PROVIDING AND LAYING PANELLING ON WALLS & PILLARS HAVING 12 MM THICK MDF BOARD EXTERIOR GRADE / 6 MM THICK PLY AND 1.0 MM TH LAMINATE FIXED ON WALL & PILLARS WITH ALUMINIUM. FRAMING OF 25MMX25MMX1.20MM THICK AT MAXIMUM 2'-0" C/C BOTHWAYS ON WALL AND PILLAR ETC COMPLETE AS DIRECTED AS PER DESIGN AND INSTRUCTION OF ARCHITECT. . THE QUOTED RATE SHALL BE APPLICABLE FOR EITHER OF THE SPECIFIED BOARD OPTIONS AS DIRECTED BY THE ARCHITECT/BANK, WITH NO EXTRA PAYMENT.				
12[a]	Providing and fixing 18 mm thick plywood of 4" height with 1.0 mm thick laminate finish runner patta on Storage Top / Table Top if required.etc complete as directed.	0.00	RMT		
12[b]	Same as above item no 12 but Providing & Fixing 3.5 mm thick Veneer with PU coating finishing over aluminium framing panelling for wall panelling etc in Manager Cabin	0.00	SQMT		
12[c]	CREATING BOX FOR FIXING AC MACHINE AND CONCEALING OF COPPER AND DRAIN PIPE AND AROUND FRONT SIDE MAIN ENTRANCE DOOR TOP, JAMBS USING 18 MM THICK MR GRADE PLYWOOD WITH 1.00 MM THICK LAMINATE TO BE FIXED OVER ALUMINIUM FRAMING OF 25 X 25 X 1.2 MM AS PER REQUIREMENT AND DRAWING ETC COMPLETE AS DIRECTED.	0.00	SQMT		
12[d]	Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0" c/c bothway as per drawing and direction with all labour and material etc complete (Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jali work as directed)	0.00	SQMT		
12[e]	Same as above but Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating paint over existing laminate central column as per drawing and direction with all labour and material etc complete (Rate shall be including CNC cutting jali work and 1mm thick blue gloss laminate behind design jali work as directed)	0.00	SQMT		
12[f]	Panelling for Display wall with 3M Vinyl glossy Film with printed design	0.00	SQMT		



	Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl glossy films with printed design fixed on wall with Aluminium framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. MDF board to be finished with 0.60 mm thick laminate or paint before laying 3M film. Only Front elevation area shall be measured for payment purpose.				
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.				
12[g]	Panelling for Digital wall with Blue / white high gloss PU Coating finishing	0.00	SQMT		
	Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. Only finished visible surface area shall be measured for payment.				
12[h]	Same as above item Panelling for Digital wall but with Blue matt finish 1 mm thick laminate finishing instead of PU paint	0.00	SQMT		
12[i]	Same as above item, Panelling for Digital wall but using 12mm thick MDF board / 6 mm thick ply without laminate finishing if required for wall paper fixing.	0.00	SQMT		
12[j]	P/A WALL PAPERS on Digital wall	0.00	SQMT		
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				
12[k]	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE	14.23	SQMT		
	PROVIDING AND FIXING 3 MM THICK ALUMINIUM COMPOSITE PANEL OF FLEXI BOND / EURO BOND / TIMEX WITH 0.25 MM FOIL WITH 50 MM X 25 MM X 1.20 MM THICK ALUMINIUM HOLLOW SECTION TRAY SYSTEM WITH MINIMUM 20 MM BENDING WITH SILICON DOW CORNING OF GE SEAL PROOF - ACP OF APPROVED INDIAN MAKE COMPLETE AS PER SELECTION AND DIRECTION OF ARCHITECT FOR FRONT FACADE FOR THE BUILDING. THIS ITEM WILL BE CARRIED OUT AS PER MANUFACTURER'S SPECIFICATIONS. RATE ALSO INCLUDES PROVIDING TRAP DOOR SHUTTER WITH HINGES, STOPPERS ETC COMPLETE AS DIRECTED. DESIGN AS PER BANK STANDARD DRAWING AND ARCHITECT'S INSTRUCTIONS ETC COMPLETE. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 OR EQUIVALENT				




	FALSE CEILING WORK				
13	P/F GYPSUM BOARD FALSE CEILING	70.92	SQMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
13[a]	Same as above item but providing and fixing of 8 mm thick Hilux board false ceiling instead of Gypsum Board for Item No-13 etc complete as per design and instruction. Only finished surface area shall be measured for payment.	0.00	SQMT		
13[b]	SAME AS ABOVE BUT PROVIDING AND FIXING OF 8 MM THICK MDF BOARD STRIP WITH BLUE SHADE HIGH GLOSS PU COATING INSTEAD OF GYPSUM BOARD FOR ITEM NO. 13 OVER TRANSACTION AREA ETC COMPLETE AS PER DESIGN AND INSTRUCTION. ONLY FINISHED SURFACE AREA SHALL BE MEASURED FOR PAYMENT.	0.00	SQMT		
13[c]	Same as above but providing and fixing 6 mm thick ply covered with 1 mm thick blue shade laminate	0.00	SQMT		
13[d]	PROVIDING AND FIXING OF ARMSTRONG MINERAL FIBRE ACOUSTICAL SUSPENDED CEILING SYSTEM WITH FINE FISSURED (MICRO LOCK) EDGE TILES WITH ARMSTRONG SILHOUETTE EXPOSED GRID	27.00	SQMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
14	SOFT BOARD	1.44	SQMT		



	PROVIDING & FIXING SOFT BOARD FOR PIN UP USING MOULDED STEAM BEECH FRAME OF 1" x 1/2" WITH 6 MM THICK COMMERCIAL PLYWOOD ON BACK SIDE AND 12MM TH SOFT BOARD ON FRONT COVERED WITH CLOTH OF SELECTED DESIGN OF BASIC RATE OF RS. 150 PER RMT. STEAM BEECH MEMBER SHALL HAVE LACQUER POLISH AS DIRECTED.				
15	SUPPLYING AND FIXING ROLLER BLIND BLACKOUT OF APPROVED MAKE WITH SELECTED FABRIC OF APPROVED DESIGN AND SHADE. (BASIC PRICE OF Rs 135=00 PER SQ.Ft EXCLUDING GST)	0.00	SQMT		
16	PROVIDING AND FIXING FROSTED POLYESTER FILM OF 3M (SCOTCHCAL 7725 - 324) OR EQUIVALENT MAKE OVER GLASS SURFACE AS PER DRAWING & DIRECTION WITH ALL LABOUR & MATERIALS TO THE SATISFACTION OF THE ARCHITECT/BANK AS PER MANUFACTURER'S SPECIFICATION. NO DEDUCTION WILL BE MADE FOR ANY CUTTING IN THE FILM.	3.00	SQMT		
17	Supplying and installation 3'-0" x 1'-9" x 1'-3" height Center Tepoy as follows.	0.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
17a	Same as above but size 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy	1.00	NO		
18	PROVIDING AND FIXING 2 NOS SHEETS OF 24"x 36" CLEAR ACRYLIC SHEETS (POSTER TO BE SANDWICHED IN BETWEEN). OUTER SHEET IS 5 MM THICK AND BEVELLED CRYSTAL EDGE POLISHED FOR 3/4" WIDE AT 8-10 DEGREES ON ALL SIDES AND THE REAR SHEET IS 5 MM THICK FLAT ETC COMPLETE AS DIRECTED.	0.00	SQMT		
18a	SAME AS ABOVE BUT OF SIZE OF 18"x 24" (POSTER TO BE SANDWICHED IN BETWEEN)	0.00	NO		
18b	SUPPLYING AND INSTALLATION SUGGESTION /COMPLAINT BOX MADE FROM 5 MM THICK ACRYLIC SHEET OF SIZE 230MM X305MM X 150MM DEPTH WITH OPENABLE HINGED SHUTTER AND SLOT FOR PUTTING SUGGESTIONS / COMPLAIN WITH LOCKABLE ARRANGEMENT AS PER DESIGN AND INSTRUCTION.	1.00	NO		
18c	P/F MIRROR				



	Providing and fixing 1'-6"x2'-0" Mirror above wash basin 6 mm thick Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.	2.00	NO		
	PAINTING WORK				
19a	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT) Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying FULL primer and putty at all heights complete as per manufacturer's specification and as directed.	0.00	SQMT		
19b	P/A DISTEMPER PAINT Providing and applying distemper paint (water base) of approved make & shade on old/new surface including scrapping/cleaning and preparation of surface for painting, applying cement based primer & FULL putty of approved make. Applying distemper paint in two or more coats to give uniform covering at all heights as directed by Engineer / Architect.	0.00	SQMT		
19c	P/A SYNTHETIC ENAMEL PAINT Providing and applying synthetic enamel paint at all heights of required shade and approved make on new / old work including scrapping / cleaning and preparation of surfaces for painting, applying primer and putty, with two or more coats of approved first quality enamel.	0.00	SQMT		
19d	P/A APEX PAINT PROVIDING AND APPLYING APEX PAINT (ASIAN PAINT ADVANCED ANTI ALGAL WEATHER PROOF EMULSION) ON NEW/OLD SURFACE AT ALL HEIGHTS AND LEVELS. WORK INCLUDES PREPARATION OF SURFACE, CLEANING AND SCRAPING BY WIRE BRUSH, FILLING CRACKS WITH "RENDROC CS"(FOSROC) AND APPLYING COAT OF HYDROPROOF LIQUID MIXED WITH WHITE CEMENT. APPLYING PRIMER COAT AS PER COMPANY SPECIFICATIONS AND APPLYING 2 OR MORE COATS OF PAINT TO GIVE UNIFORM SHADE AT ALL LEVELS COMPLETE.	0.00	SQMT		
19e	Providing and applying Texture paint of approved shade of Asian /Heritage/Berger brand on internal walls. Rate includes surfaces preparation, applying necessary coats of paint to obtain Uniform and even finish.	0.00	SQMT		



20	P & S of Visitors sofa. The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 ½" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with <u>basic rate of Rs.750/- per meter</u> . It will have upholstered handles / brush finish S.S. legs. <u>outer length with armrest</u> will be considered for measurement purpose.	0.00	RMT		
21	ARTIFICIAL PLANTS				
	Providing and fixing Artificial Plants/Creepers as per direction. - Big Plant - 1, Small Plant - 3, Creepers - 5 & Bonsai - 1.	0.00	NO		
22	PLANTER BOX				
	PROVIDING AND FIXING STAINLESS STEEL PLANTER BOX OF NECESSARY REQUIREMENTS & SIZE & DESIGN. THIS ITEM ALSO INCLUDES MARBLE CHIPS STONE ETC. COMPLETE.	0.00	NO		
	TOTAL COST "A"				
Note:					
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabelling and No extra amount shall be paid for this				
[b]	ALL INTERNAL SURFACE (NON VISIBLE SURFACES) SHALL BE PROVIDED WITH THE 0.60 MM THICK BALANCING LAMINATE OF APPROVED MAKE & SHADE IN THE ALL S.W COUNTERS/TABLES/ CREDENZA, STORAGE CUP BOARD ETC.				
	SUMMARY				
[A]	FURNISHING WORK				
	NET TOTAL COST [A]				



